

## Commissioning of SH5K-20 Hybrid Inverters

### Disclaimer


The material in this document has been prepared by Sungrow Australia Group Pty. Ltd. ABN 76 168 258 679 and is intended as a guideline to assist solar installers for troubleshooting. It is not a statement or advice on any of the Electrical or Solar Industry standards or guidelines. Please observe all OH&S regulations when working on Sungrow equipment.

The commissioning phase of the SH5K-20 inverter is straight forward and simple. All settings are done from the front panel, and there is no longer any need to manually enter the battery details – the system will automatically detect a powered-up battery.


On first initialisation, the following will appear on the LCD screen.



Enter to set/check the country code



Enter "AU" for AS/NZS 4777 as default



Select appropriate DNSP, or manually enter grid protection parameters (Default DNSP power factor settings will be loaded)

Grid company Code	Company
AG	AusGrid, NSW
EE	Ergon Energy, QLD
EG	Energex, QLD
PN	SA Power Networks, SA
PC	Powercor, VIC
WP	Western Power, WA
Default	Company not mentioned above



Enter to save



Check / set time and date as required




Incorrect time setting will affect monitoring



Setting the Zero Export



'ON' = No power exported. "OFF" = All power exported. "PARTIAL" = set by watts



Default = Partial 5000 watts



Set Reactive power if required. Note: Grid settings already have State requirements loaded when DNSP selected.



Set if required



Set battery discharge times (only available if battery connected)

Bat Usage Time

- ▶ Weekday Usage
- Weekend Usage

Weekday and weekend time zones available

- ▶ Start Time1 00:00
- End Time1 24:00
- Start Time2 00:00
- End Time2 24:00

Generally, only set if customer is on TOU metering. Otherwise leave as default.

Initial Settings 2/3

- Reactive Power
- Bat Usage Time
- ▶ EPS Setting

EPS (Off-Grid) setting only if EPS box connected and maximum 3 kW output under EPS mode.

EPS Setting

- Disable
- Enable

Enable and enter


Must install an EPS box if the EPS function is enabled!



Enter to save





Enter to test Earth Fault alarm



Enter to save and exit

There are a couple of subsequent settings that may be required depending on the configuration.


If there is an existing PV system on the same phase, it must be enabled in the settings otherwise some errors (error 084) may occur. This also allows battery charging from existing system.




Enter



Password = 111 (Enter)




Enter 'Existing System'



Enable and enter





Enter the AC power of the total inverters **on the same phase only** (you can also change the export limit here)



Enter to save


There may also be a requirement from the customer to reserve a set amount of battery capacity to be available in the event of a blackout. This will quarantine a pre-set amount and will take that amount out of the daily cycle capacity. This is only available after inverter has restarted with battery set.




Enter into settings




Password = 111



EPS setting



Enable



Enter to confirm



Enter desired value, based on a calculation of total capacity, load, and how long backup is required for.



Enter to save and finish.

Once the commissioning is completed, please follow the below checklists to test the system.

1. The inverter only shows **green light ON** and **status shows Running**; if the existing solar power is sufficient, the system should charge the battery.



2. Turn **more house load ON** to see whether the battery discharges.
3. If the EPS box (or backup) is installed, **turn off the grid supply main to test the Off-grid function**; if the function is OK and then turn the grid supply main to ON.
4. After completing these testing, the system should run OK.

For any assistance, please contact Sungrow Service Department on 1800 786 476.